

Improvements to the Missouri River
Wastewater
Treatment PlantSchedule B Project

Public Meeting
June 4, 2013
South Omaha Public Library



Agenda

- Welcome and Introductions
- CSO Program Overview
- Missouri River WWTP-Schedule B
 - Project Overview
 - Schedule
 - Contacts
- Status Update on Related CSO Projects and Missouri River WWTP Activities





CSO Program Overview



Challenges Facing Omaha

Meeting the increased requirements of the federal Clean Water Act


Balancing the following needs:

- Regulatory compliance
- Economic affordability
- Community acceptance






772+ CSO Communities Nationwide





Omaha's Regional Sewer System

- 1,950 miles of sewers
 - Eastern half combined
 - Western half separate
- 43 sq. mi combined sewer area
 - 28,000 acres
 - 6,200 sq. blocks
- 29 CSO outfalls
 - 10 to Papio Creek
 - 19 to Missouri River
 - 3 recently eliminated
 - 5 more to be eliminated





Omaha's Regional Sewer System

- Two regional treatment plants
- 10 wholesale users
- 275 sq. mi drainage area
- 600,000 service population





Program Benefits

- Reduce overflows of raw sewage to our streams; improve water quality
- Continue our efforts to eliminate sewer
 - backups into basements
- Replace aging sewer, gas, water and street infrastructure






Program Benefits

- Integrate infrastructure upgrades with continued redevelopment
- Improve drainage and reduce flooding





Five Major Elements of Final Long Term Control Plan





Targeted Sewer Separation Projects



Two High-Rate
Treatment Facilities



One Deep Conveyance Tunnel




Five Major Elements of Final Long Term Control Plan





Two Underground Storage Tanks



One Deep Conveyance Sewer



New Consent Order Timeline





Program Status

- \$110M of construction under contract
- \$415M of construction under design
- \$150M of construction added in 2013
- Refining revised LTCP schedule
- Sewer rates for 2015-2018 under study
- Affordability Assessment update
- Green Infrastructure study
- NETV documentary airing



Funding the Program

 The federal mandate for the Omaha system is to increase wet weather capacity to reduce sewage overflows

All area Customers

Contribute to the overflows

Benefit from improvements to regional water quality

Will help fund the improvements



LTCP Costs (2009 Dollars)


Project Category	Program Cost
Deep Tunnel Project	\$ 442,082,000
Minne Lusa Stormwater Collector Projects	\$ 112,750,000
High Rate Treatment Projects	\$ 126,326,000
South Interceptor Force Main Project	\$ 77,249,000
MRWWTP Improvements	\$ 90,934,000
Lift Station Projects	\$ 131,196,000
Storage Structure Projects	\$ 30,878,000
Sewer Separation Projects	\$ 614,361,000
Miscellaneous Projects	\$ 36,448,000
TOTAL	\$ 1,662,224,000

Note: Estimated Total Cost in 2012 dollars ~\$2B






Site Location






What Happens at the Missouri River WWTP?



- Preliminary Treatment Headworks Facility
 - Screening and Grit Removal
 - Remove large objects such as rags, paper, and plastics
 - Remove sand, gravel, and other heavy solid materials
 - Permit Requirements
 - · Flow sampling and measurement
- Primary Treatment Primary Clarifiers
 - Settleable Solids Removal



What Happens at the Missouri River WWTP?




- Secondary Treatment Biological Treatment
 - Trickling Filters
 - Clarification
 - Remove organic matter from wastewater
- Disinfection
 - Chlorination
 - Dechlorination
 - Kill bacteria (E.Coli) using Sodium Hypochlorite
 - Remove active chlorine using Sodium Bisulfite



CSO Project Need

- Missouri River WWTP current capacity not large enough for future wet weather flow
- Increase capacity to accommodate
 - Additional industrial flows
 - Reliable secondary treatment
 - Preliminary and primary treatment for 150 MGD design flow rate
 - Disinfect remaining flow



WWTP Project Need


Enable future protection of WWTP from flooding events




Site Improvement Plan

Schedule A Facilities

Schedule B New Facilities Schedule B Upgraded Facilities







- In-Plant Lift Station
 - Reliably pump 18 MGD to Municipal Headworks
 Facility


Municipal Headworks Facility

- Preliminary treatment
- Take flow from several existing sources and the future deep tunnel

Municipal Primary Splitter Structure

Split flow to primary treatment





- **Municipal Primary Clarifiers**
 - Primary treatment


- CSO 102
 Chlorination and
 Dechlorination
 Facility
 - Chemical storage
 - Disinfection of primary effluent
 - 126 E.Coli Organisms/ 100 mL
 - 0.137 mg/L of Total Residual Chlorine



- Odor Control for main sources
 - Municipal Headworks
 - Biological treatment of odors
 - Improved odor control over existing facility
 - More air treated
 - Better at removing complex compounds
 - Primary Clarifiers
 - Maximize use of existing odor control



Flood Protection






Buildings





Potential Impacts to Wetlands

- Evaluated alternatives with no wetlands impacts and they were expensive
- Wetlands impacts necessary to construct facilities
- Minimized impacts during design, 2.24 acres
- Submitted 404 Permit Application in May



Community Enhancements

- Community Enhancements
 - Secure site with no access to the public
 - Community enhancements, as defined by the CSO Program, do not apply




Green Solutions for Stormwater Management

- Vegetated Swales
 - Open, shallow channel with vegetation covering the side slopes and bottom
- Dry Ponds
 - Pond with no permanent pool
 - Relies upon detention storage
- Filter Strips
 - Evenly sloped vegetated areas adjacent to impervious areas
 - Treat stormwater by filtering it through vegetation



Schedule



August 2013 – January 2014

Final Design

Construction and Start-Up

February 2014 – October 2017

2013 2014 2015 2016 2017



How Will This Project Effect My Neighborhood or Business?

Trucking Routes During Construction





Contact Information

City of Omaha

Murthy Koti

Traffic Contact

murthy.koti@ci.omaha.ne.us

(402) 444-5220

Rick Murch

Project Manager

rick.murch@ci.omaha.ne.us

(402) 444-3915, x-204

Engineer

Matt Krumholz

Project Manager

matt.krumholz@ch2m.com

(720) 286-2747

Program Management Team

Scott Aurit

Project Coordinator

scott.aurit@hdrinc.com

(402) 926-7082

Linda Lovgren

Public Relations Facilitator

lovgren@lovgren.com

(402) 397-7158

Pat Nelson

Compliance Coordinator

pat.nelson@ch2m.com

(402) 609-7512



QUESTIONS ON MISSOURI RIVER WWTP – SCHEDULE B






Related Projects

- South Omaha Industrial Area Projects
 - Force Main and Gravity Sewer
 - Lift Station
- Missouri River WWTP-Schedule A Project
 - New Grit Removal and Primary Clarifiers for Industrial Flows
- Missouri River WWTP Berm Removal



Sewer System Improvements




Project Locations and Routes



South Omaha Industrial Area Projects Status

- Force Main and Gravity
 Sewer
 - 97 Percent Complete
- Lift Station
 - Approximately 80Percent Complete
- Both Projects
 Substantially Complete
 in September 2013









Missouri River WWTP-Schedule A

- Increase capacity to accommodate
 - Additional industrial flows
 - Reliable secondary treatment

Construction complete in 2013



Berm Removal

Was utilized for flood protection in 2011

Removal planned June to Oct

Excavation and hauling project



QUESTIONS

