Burt Izard Lift Station Improvements

September 20, 2016







Opportunities & Benefits

- Reduce overflows of raw sewage to our streams; improve water quality
- Continue our efforts to eliminate sewer backups into basements
- Replace aging sewer, gas, water and street infrastructure
- Urban revitalization and development



Wet weather inflows exceed the CSS capacity and trigger a CSO





CSO Program Area

- 43 sq mi combined sewer area
 6,200 sq blocks
- 28 CSO outfalls

 9 to Papio Creek
 19 to Missouri River
 4 eliminated





New Consent Order Timeline







Long Term Control Plan



Major Elements of the Long Term Control Plan



Targeted Sewer Separation Projects



High Rate Treatment Facilities





Major Elements of Final Long Term Control Plan



Underground Storage Tanks





CSO Controls: Tunnel

- Deep Conveyance Tunnel
 - o Length: 5.4 miles
 - Diameter: 17 feet
 - o Depth: 170 feet
 - o Drop shafts: 5





Green Solutions





Conveyance (Swales)



Adams Park Wetland Zones





LOWLAND GRASS



WETLAND MEADOW



EMERGENT WETLAND



Spring Lake Park



Syndicate Park 1920's

New Green Solution



Fontenelle Park





Saddle Creek Green Infrastructure







Program Funding



Funding the Program

Financed with 30-year bonds Funded with sewer fees





Program Costs 2015 Dollars \$2.2 Billion



Clean Solutions for Omal

Average Residential Sewer Bills: Omaha vs. National Average





Average Industrial Sewer Bills: Omaha vs. National Average





CSO Public Benefits











What is the Project?



What is a Lift Station?





Project Purpose

Increase volume of flow conveyed to the Missouri River Wastewater Treatment Plant in conjunction with the improvements to the South Interceptor Forcemain Project.





Scope of Work

- Flow improvements to the lift station
- Improvements inside the Grit Building
- New bar screens
- New pumps, piping, and valves
- Upgrades to the electrical power feed
- New electrical and controls inside the lift station



Burt Izard Lift Station



Site Location and Area of Work





Site Plan



What to Expect

- Most work inside facilities
- Electrical/transformer work
- Bypass Pumping
- Forcemain Tie-in
- Construction Deliveries





Burt Izard Project Schedule



Project Schedule

- Public Discussion: Fall 2016
- Design completion: Early 2017
- Bidding: Spring 2017
- Construction Begins: Summer 2017
- Construction Ends: Fall 2018



Website: <u>www.OmahaCSO.com</u> CSO Hotline: 402-341-0235







O! ne News Google Calendar
 Annual Report
 The arrowal report for the
 Or 1, 2014 - 6929 (2015
 can be read by visiting this page.

FOLLOW THE OMAHA CSO PROGRAM ON TWITTER! Tweets by Comparison



CSO Public Display





Questions & Discussion

• Linda Lovgren

Public Participation Facilitator 402-397-7158 info@omahacso.com

Suzie Carpenter
 Project Manager
 816-412-3108

