

Spring Street Sewer Separation Project



COMPLETED DATE:

- Q1 2010



COST AT COMPLETION:

- \$114,000



PROJECT LOCATION:

- In the South Interceptor Basin, south of Interstate 80 and east of the Henry Doorly Zoo and Aquarium



This project included construction of a sanitary sewer to connect to the existing Spring Street Lift Station.

This project provided sewer separation to an area of the South Interceptor basin. Sanitary flows were directed to the Spring Street Lift Station through the construction of a new sanitary sewer. This allowed the existing sewer to be converted to a stormwater sewer.

The sanitary flow will flow by gravity to the Blake Street Lift Station and continue to the Missouri River Water Resource Recovery Facility for treatment.

This project reduces overall flow to the downstream combined system. Additionally, CSO discharge point 113 was eliminated.

